

REPORT DOCUMENTATION PAGE					<i>Form Approved</i> <i>OMB No. 0704-0188</i>	
The public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing the burden, to the Department of Defense, Executive Services and Communications Directorate (0704-0188). Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to any penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number.						
PLEASE DO NOT RETURN YOUR FORM TO THE ABOVE ORGANIZATION.						
1. REPORT DATE (DD-MM-YYYY) 11-03-2014		2. REPORT TYPE Journal Article			3. DATES COVERED (From - To)	
4. TITLE AND SUBTITLE Submesoscale dispersion in the vicinity of the Deepwater Horizon spill					5a. CONTRACT NUMBER	
					5b. GRANT NUMBER	
					5c. PROGRAM ELEMENT NUMBER	
6. AUTHOR(S) Andrew C. Poje, Tamay M. Özgökmen, Bruce L. Lipphardt, Jr., Brian K. Haus, Edward H. Ryan, Angelique C. Haza, Gregg A. Jacobs, A. J. H. M. Reniers, Maria Josefina Olascoaga, Guillaume Novelli, Annalisa Griffa, Francisco J. Beron-Vera, Shuyi S. Chen, Emanuel Coelho, Patrick J. Hogan, Albert D. Kirwan, Jr., Helga S. Huntley, and Arthur J. Mariano					5d. PROJECT NUMBER	
					5e. TASK NUMBER	
					5f. WORK UNIT NUMBER 73-4799-02-5	
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) Naval Research Laboratory Oceanography Division Stennis Space Center, MS 39529-5004					8. PERFORMING ORGANIZATION REPORT NUMBER NRL/JA/7320--14-2295	
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES) Office of Naval Research One Liberty Center 875 North Randolph Street, Suite 1425 Arlington, VA 22203-1995					10. SPONSOR/MONITOR'S ACRONYM(S) Univ of Miami	
					11. SPONSOR/MONITOR'S REPORT NUMBER(S)	
12. DISTRIBUTION/AVAILABILITY STATEMENT Approved for public release, distribution is unlimited.						
13. SUPPLEMENTARY NOTES						
14. ABSTRACT Reliable forecasts for the dispersion of oceanic contamination are important for coastal ecosystems, society, and the economy as evidenced by the Deepwater Horizon oil spill in the Gulf of Mexico in 2010 and the Fukushima nuclear plant incident in the Pacific Ocean in 2011. Accurate prediction of pollutant pathways and concentrations at the ocean surface requires understanding ocean dynamics over a broad range of spatial scales. Fundamental questions concerning the structure of the velocity field at the submesoscales (100 m to tens of kilometers, hours to days) remain unresolved due to a lack of synoptic measurements at these scales. Using high-frequency position data provided by the near-simultaneous release of hundreds of accurately tracked surface drifters, we study the structure of submesoscale surface velocity fluctuations in the Northern Gulf of Mexico. Observed two-point statistics confirm the accuracy of classic turbulence scaling laws at 200-m to 50-km scales and clearly indicate that dispersion at the submesoscales is local, driven predominantly by energetic submesoscale fluctuations. The results demonstrate the feasibility and utility of deploying large clusters of drifting instruments to provide synoptic observations of spatial variability of the ocean surface velocity field. Our findings allow quantification of the submesoscale-driven dispersion missing in current operational circulation models and satellite altimeter-derived velocity fields.						
15. SUBJECT TERMS ocean dispersion; pollutant patterns; geophysical turbulence; Lagrangian transport						
16. SECURITY CLASSIFICATION OF:			17. LIMITATION OF ABSTRACT UU	18. NUMBER OF PAGES 06	19a. NAME OF RESPONSIBLE PERSON Gregg A. Jacobs	
a. REPORT Unclassified	b. ABSTRACT Unclassified	c. THIS PAGE Unclassified			19b. TELEPHONE NUMBER (Include area code) (228) 688-4720	

Reset

PUBLICATION OR PRESENTATION RELEASE REQUEST

ubley: 9359

NRLINST 5600.2

14-1231-3116

Ref: (a) NRL Instruction 5600.2 (b) NRL Instruction 5510.40D	() Abstract only, published () Book () Conference Proceedings (refereed)	() Abstract only, not published () Book chapter () Conference Proceedings (not refereed)	STRN <u>NRL/JA/7320-14-2295</u>
Encl: (1) Two copies of subject paper (or abstract)	() Invited speaker (X) Journal article (refereed) () Oral Presentation, published () Other, explain	() Multimedia report () Journal article (not refereed) () Oral Presentation, not published	Route Sheet No. <u>7320/</u> Job Order No. <u>73-4799-02-5</u> Classification <u>X</u> <u>U</u> <u>C</u> Sponsor <u>U of Miami</u> approval obtained <u>yes</u> <u>X</u> <u>no</u>

Title of Paper or Presentation

Submesoscale dispersion in the vicinity of the Deepwater Horizon spill

Author(s) Name(s) (First, MI, Last), Code, Affiliation if not NRL

A. Poje The City Univ. of New York T. Ozgokmen Univ. of Miami Bruce Lipphardt Univ. of Delaware B.K. Haus Univ. of Miami E. Ryan Univ. of Miami
 A. Haza Univ. of Miami Gregg A. Jacobs 7320 A. Reniers Univ. of Miami J. Olascoaga Univ. of Miami G. Novelli Univ. of Miami A. Griffo Univ. of Miami
 F.J. Beron-Vera Univ. of Miami Shuyi Chen Univ. of Miami Patrick J. Hogan 7323 Emanuel Coelho University of New Orleans D. Kirwan Univ. of Miami
 H. Huntley Univ. of Delaware A. Mariano Univ. of Miami

It is intended to offer this paper to the

(Name of Conference)

(Date, Place and Classification of Conference)

and/or for publication in Proceedings of the National Academy of Sciences Journal

(Name and Classification of Publication)

(Name of Publisher)

After presentation or publication, pertinent publication/presentation data will be entered in the publications data base, in accordance with reference (a).

It is the opinion of the author that the subject paper (is) (is not X) classified, in accordance with reference (b).This paper does not violate any disclosure of trade secrets or suggestions of outside individuals or concerns which have been communicated to the Laboratory in confidence. This paper (does) (does not X) contain any militarily critical technology.This subject paper (has) (has never X) been incorporated in an official NRL Report.

Gregg A. Jacobs, 7320

Name and Code (Principal Author)

(Signature)

CODE	SIGNATURE	DATE	COMMENTS
Author(s) Gregg Jacobs, 7320		9/4/2014	Need by 16 Sep 2014
			Publicly accessible sources used for this publication
			This is a Final Security Review. Any changes made in the document after approved by Code 1231, nullify the Security Review.
Section Head			
Branch Head			
Division Head			
Ruth H. Preller, 7300		9/4/14	Sources Approval Attached 1. Release of this paper is approved. 2. To the best knowledge of this Division, the subject matter of this paper (has <u> </u>) (has never <u>X</u>) been classified.
Security, Code 1231		9/4/14	1. Paper or abstract was released. 2. A copy is filed in this office.
Office of Counsel, Code 1008.3		9/18/14	
ADOR/Director NCST E. R. Franchi, 7000			
Public Affairs (Unclassified/ Unlimited Only), Code 7030.4		9-17-14	
Division, Code			
Author, Code			

5 SEP 14 PM 1:44

S

Submesoscale dispersion in the vicinity of the *Deepwater Horizon* spill

Andrew C. Poje^a, Tamay M. Özgökmen^{b,1}, Bruce L. Lipphardt, Jr.^c, Brian K. Haus^b, Edward H. Ryan^b, Angelique C. Haza^b, Gregg A. Jacobs^d, A. J. H. M. Reniers^b, Maria Josefina Olascoaga^b, Guillaume Novelli^b, Annalisa Griffa^e, Francisco J. Beron-Vera^b, Shuyi S. Chen^b, Emanuel Coelho^d, Patrick J. Hogan^d, Albert D. Kirwan, Jr.^c, Helga S. Huntley^c, and Arthur J. Mariano^b

^aDepartment of Mathematics, Graduate Physics Program, College of Staten Island, City University of New York, New York, NY 10314; ^bDepartment of Ocean Sciences, Rosenstiel School of Marine and Atmospheric Sciences, University of Miami, Miami, FL 33176; ^cSchool of Marine Science and Policy, University of Delaware, Newark, DE 19716; ^dOcean Dynamics and Prediction, Naval Research Laboratory, Stennis Space Center, Hancock County, MS 39529; and ^eIstituto di Scienze Marine, Consiglio Nazionale delle Ricerche, 19032 La Spezia, Italy

Edited by Carl Wunsch, Harvard University, Cambridge, MA, and approved July 24, 2014 (received for review February 7, 2014)

Reliable forecasts for the dispersion of oceanic contamination are important for coastal ecosystems, society, and the economy as evidenced by the *Deepwater Horizon* oil spill in the Gulf of Mexico in 2010 and the Fukushima nuclear plant incident in the Pacific Ocean in 2011. Accurate prediction of pollutant pathways and concentrations at the ocean surface requires understanding ocean dynamics over a broad range of spatial scales. Fundamental questions concerning the structure of the velocity field at the submesoscales (100 m to tens of kilometers, hours to days) remain unresolved due to a lack of synoptic measurements at these scales. Using high-frequency position data provided by the near-simultaneous release of hundreds of accurately tracked surface drifters, we study the structure of submesoscale surface velocity fluctuations in the Northern Gulf of Mexico. Observed two-point statistics confirm the accuracy of classic turbulence scaling laws at 200-m to 50-km scales and clearly indicate that dispersion at the submesoscales is local, driven predominantly by energetic submesoscale fluctuations. The results demonstrate the feasibility and utility of deploying large clusters of drifting instruments to provide synoptic observations of spatial variability of the ocean surface velocity field. Our findings allow quantification of the submesoscale-driven dispersion missing in current operational circulation models and satellite altimeter-derived velocity fields.

ocean dispersion | pollutant patterns | geophysical turbulence | Lagrangian transport

The *Deepwater Horizon* (DwH) incident was the largest accidental oil spill into marine waters in history with some 4.4 million barrels released into the DeSoto Canyon of the northern Gulf of Mexico (GoM) from a subsurface pipe over ~84 d in the spring and summer of 2010 (1). Primary scientific questions, with immediate practical implications, arising from such catastrophic pollutant injection events are the path, speed, and spreading rate of the pollutant patch. Accurate prediction requires knowledge of the ocean flow field at all relevant temporal and spatial scales. Whereas ocean general circulation models were widely used during and after the DwH incident (2–6), such models only capture the main mesoscale processes (spatial scale larger than 10 km) in the GoM. The main factors controlling surface dispersion in the DeSoto Canyon region remain unclear. The region lies between the mesoscale eddy-driven deep water GoM (7) and the wind-driven shelf (8) while also being subject to the buoyancy input of the Mississippi River plume during the spring and summer months (9). Images provided by the large amounts of surface oil produced in the DwH incident revealed a rich array of flow patterns (10) showing organization of surface oil not only by mesoscale straining into the loop current “Eddy Franklin,” but also by submesoscale processes. Such processes operate at spatial scales and involve physics not currently captured in operational circulation models. Submesoscale motions, where they exist, can directly influence the

local transport of biogeochemical tracers (11, 12) and provide pathways for energy transfer from the wind-forced mesoscales to the dissipative microscales (13–15). Dynamics at the submesoscales have been the subject of recent research (16–20). However, the investigation of their effect on ocean transport has been predominantly modeling based (13, 21–23) and synoptic observations, at adequate spatial and temporal resolutions, are rare (24, 25). The mechanisms responsible for the establishment, maintenance, and energetics of such features in the Gulf of Mexico remain unclear.

Instantaneous measurement of all representative spatiotemporal scales of the ocean state is notoriously difficult (26). As previously reviewed (27), traditional observing systems are not ideal for synoptic sampling of near-surface flows at the submesoscale. Owing to the large spacing between ground tracks (28) and along-track signal contamination from high-frequency motions (29), gridded altimeter-derived sea level anomalies only resolve the largest submesoscale motions. Long time-series ship-track current measurements attain similar, larger than 2 km, spatial resolutions, and require averaging the observations over evolving ocean states (30). Simultaneous, two-point acoustic Doppler current profiler measurements from pairs of ships (25) provide sufficient resolution to show the existence of energetic submesoscale fluctuations in the mixed layer, but do not explicitly quantify the scale-dependent transport induced by such motions at the surface. Lagrangian experiments, centered on tracking large numbers of water-following instruments, provide the most feasible means of obtaining spatially distributed,

Significance

We report here on results obtained from the largest upper-ocean dispersion field program conducted to date. The observations provided, for the first time to our knowledge, an accurate and nearly simultaneous description of the ocean surface velocity field on spatial scales ranging from 100 m to 100 km. We show conclusively that ocean flows contain significant energy at scales below 10 km and that their fluctuations dictate the initial spread of tracer/pollutant clouds. Neither state-of-the-art operational models nor satellite altimeters capture the flows needed for accurately estimating the dispersion of surface particles.

Author contributions: A.C.P., T.M.Ö., B.K.H., E.H.R., A.C.H., G.A.J., A.G., S.S.C., A.D.K., and H.S.H. designed research; A.C.P., T.M.Ö., B.L.L., B.K.H., E.H.R., G.A.J., A.J.H.M.R., M.J.O., G.N., S.S.C., E.C., and P.J.H. performed research; A.C.P., T.M.Ö., B.L.L., B.K.H., A.C.H., G.A.J., G.N., A.G., F.J.B.-V., E.C., A.D.K., and A.J.M. contributed new reagents/analytic tools; A.C.P., T.M.Ö., B.L.L., E.H.R., A.C.H., G.A.J., A.J.H.M.R., M.J.O., F.J.B.-V., and E.C. analyzed data; and A.C.P. and T.M.Ö. wrote the paper.

The authors declare no conflict of interest.

This article is a PNAS Direct Submission.

Freely available online through the PNAS open access option.

¹To whom correspondence should be addressed. Email: tozgekmen@gmail.com.

launched in less saline water remain within the western canyon for considerably longer times.

Spatial and temporal distributions of basic dispersion statistics for four drifter groups are shown in Fig. 4. The *S2* launch has been split into two groups based on residence time and surface salinity characteristics: drifters launched in low surface salinity water with residence times greater than 7 d (referred to as MRO drifters) and those launched in higher surface salinity water with short residence times. Center of mass trajectories for each group (symbol marking every 3 d) as well as dispersion ellipses indicating the size and orientation of the SD of the relative dispersion of drifters about the cluster center of mass are plotted. Observations confirm the disparity between slow, isotropic dispersion inside the canyon and rapid stretching outside.

The top panels in Fig. 5 show relative dispersion curves [here $D(t)$] for *S1* and *S2* conditioned on the initial separation distance of drifter pairs. Initial separation bins are centered at 0.1, 0.5, 5, and 10 km. Data densities range from 48 drifter pairs for the 0.1-km *S1* bin to 1,034 pairs for the 10-km *S1* bin. Error bars, shown for the smallest initial separations in *S1*, were computed from standard 95% confidence intervals produced by 2,000 bootstrapped samples at each time. Both launches indicate that initial growth depends strongly on the initial separation scale with faster growth rates for smaller separations. In the *S1* launch, which was entirely confined to the canyon for 1 wk, dispersion from initial scales below 1 km is arrested at ~8-km length scales, whereas dispersion from initial scales above 1 km shows arrest at ~30-km length scales. All curves indicate considerable energy at near-inertial frequencies. Similar behavior is observed in the *S2* data for the smallest separation scale. Corresponding dispersion curves derived from artificial drifters (launched at the same initial time and position as the GLAD drifters) advected by the geostrophic velocity field derived from AVISO gridded altimeter data do not exhibit this pattern. Neither relative nor absolute dispersion metrics for any of the drifter launches exhibited asymptotic behavior 28 d after release.

Scale-dependent dispersion results are displayed in Fig. 5, *Bottom*, where, for all three clusters, the dispersion rate given by the time-scale $\lambda(r) = \Delta v(r)/r$ scales with $r^{-\beta}$, $\beta \neq 0$ for separation scales below 10 km. The observed exponent in each case is consistent




Fig. 4. Dispersion ellipses. Trajectories and dispersion ellipses for *S1* (blue) and *T1* (yellow). Launch *S2* has been separated into two groups: drifters initialized in MRO water with residence times in the canyon longer than 7 d (red) and those with residence times in the canyon less than 7 d (green).




Fig. 5. Dispersion diagrams from GLAD in comparison with NCOM and AVISO. Time dependence of the relative dispersion, $D(t)$, for four different initial separation distances for the *S1* (Top) and *S2* (Middle) launches. For comparison, data from identical launches advected using geostrophic velocities produced by AVISO altimeter data are shown in red. (Bottom) The scale-dependent pair separation rate as function of separation distance for the three launches (*S1*, *S2*, and *T1*) shown in solid symbols with corresponding model results from a 3-km resolution NCOM simulation for *S1* and *S2* shown in open symbols. The slope indicates the Richardson regime, $\Delta v/r \sim r^{-2/3}$.

with Richardson's two-thirds law and a local dispersion regime where the underlying Eulerian kinetic energy spectrum scales are considerably shallower than the $E(k) \sim k^{-3}$ spectrum expected in an enstrophy cascading regime. Comparison of dispersion rates for synthetic drifters launched at identical locations and times to those in *S1* and *S2*, and advected by a data-assimilating, operational model (Navy Coastal Ocean Model, NCOM) simulation of the gulf show reasonable agreement with data at mesoscales ($r > 10$ km), but poor agreement at submesoscales where the model fields necessarily impose steep spectral decay near the model grid spacing. In contrast to the situation where small-scale dispersion is dominated by the strain of large scale, nearly 2D ocean flows, the observations clearly indicate the presence of energetic, local

contributions to surface relative dispersion on scales <10 km in the DeSoto Canyon region. As such, the observed measures at the submesoscales show considerably faster relative dispersion than that seen in either altimetry-derived or model-based velocity fields.

Following Richardson's original work (33), the increased rate of spread of a growing contaminant patch can be quantified by a scale-dependent relative diffusivity, $K(l)$, defined by $\frac{\partial q}{\partial t} = \frac{\partial}{\partial l} K(l) \frac{\partial q}{\partial l}$, where $q(l, t)$ is the distribution of separation lengths, l . Richardson's original empirical fit for atmospheric data, $K(l) \propto l^{4/3}$, was also derived by Obukhov (42), from similarity theory for turbulence with a forward energy cascade.

Dye-based observations estimate the diffusivity, $K_a(l)$, from area growth rates defined by fitting Gaussian ellipses to the evolving concentration patch observed along ship tracks (43), $4K_a = d\sigma^2/dt$, where $\sigma^2(t) = 2\sigma_a\sigma_b$ and (σ_a, σ_b) measure the major and minor axes of the ellipse. The scale-dependent diffusivity is typically estimated by assuming a fixed value of K_a and integrating to arrive at $K_a(l) = \sigma^2(t)/4t$ where, following Okubo (36), the scale length is given by $l = 3\sigma$. The left and bottom axes of Fig. 6 show the scale-dependent relative diffusivity defined this way as calculated from the dispersion ellipses observed during the S1 launch (Fig. 4). The single launch drifter estimates, plotted every 12 h starting 4 d after the launch, are shown in solid black squares, whereas the colored filled symbols show Okubo's compilation of individual dye experiments spanning a number of oceans over the course of several years. The magnitudes of the drifter-based diffusivity values are remarkably consistent with traditional dye-based observations and clearly extend $K_a(l) \sim l^{4/3}$ Richardson–Obukhov scaling to larger scales.

The above estimates of $K_d(\sigma)$ rely on fitting observed distributions with Gaussian ellipses. To investigate diffusivity scaling over the full range of separation scales available in the drifter data, we also examine a Lagrangian upper-bound diffusivity estimate based on classic mixing length arguments. The line marked by solid black circles in Fig. 6 shows $K_L(r) = r\Delta v(r)$ for the S1 launch. Also shown are uncertainty estimates given by the 95% confidence intervals produced by 500 bootstrapped samples of 200 randomly chosen times during the 28-d launch. The observations are well fit by classical Richardson–Obukhov scaling over the entire 200-m to 100-km range of available separation scales.

Conclusions

Large numbers of accurate, high-frequency Lagrangian instruments launched nearly simultaneously provide an effective means for quantifying scale-dependent dispersion at the ocean's surface. In the DeSoto Canyon region, an energetic submesoscale field clearly produces local dispersion at ~ 100 -m scales, which is not captured by ocean surface velocity fields derived from current satellite altimetry or operational ocean models. The high energy of the observed submesoscale field has significant implications for both predictive modeling of oceanic pollutant discharges in this region as well as for understanding overall mechanisms for energy transfer in the ocean. Whether the predominance of submesoscale fluctuations in setting local dispersion properties is an inherent surface feature of the global ocean or is instead a confined result due to the complexities of local forcing mechanisms in the DeSoto Canyon region, can be directly




Fig. 6. Scale-dependent relative diffusivities. Lower left axes: Tracer-based diffusivity estimates based on fitting ellipses. The solid red, green, and blue symbols show Okubo (36) estimates of $K_a(3\sigma) = \sigma^2/4t$. Corresponding estimates from the S1 drifter data are shown by solid black squares. Upper right axes: Scale-dependent mixing length diffusivities, $K_L(r) = r\Delta v(r)$, observed in S1 launch plotted with uncertainty estimates in solid black lines and filled black circles. Richardson–Obukhov scaling law, $K_L(r) \sim r^{4/3}$ is indicated.

addressed by conducting similar large-scale, synoptic Lagrangian observational programs in other locations.

Materials and Methods

The GLAD program was based on 300 GPS-equipped CODE drifters with nominal position accuracy of 6.4 m and battery life exceeding 2 mo. A special agreement was made with the Globalstar company to retrieve the positions at 5-min intervals. Postprocessing consisted of identifying inconsistent short-term position sequences near large reception gaps and the removal of outliers in position or velocity magnitude and rotation. Data gaps were filled using a noncausal spline interpolation, and the clean drifter position data were then low-pass filtered with a 1-h cutoff and resampled at uniform 15-min intervals. The GLAD drifter trajectory dataset used here is publicly available (44).

Along-track salinity was collected with an on-board flow-through system using a Seabird thermosalinograph (SBEMicroTSG45) and external temperature sensor (SBETemp38) located ~2 m below the water level at the ship's bow. Salinity, expressed in practical salinity units (PSU) calculated using the practical salinity scale (PSS) equations, has an estimated initial accuracy of 0.005 PSU and monthly drift of <0.003 PSU. Simultaneous salinity and 3-m accurate ship position (via an onboard Furuno GP90) were logged at 5-s intervals.

The geostrophic velocity field is assumed to be of the form $v(x, t) = g f(x_2) \nabla^{-1} \eta(x, t) + \nabla \phi(x, t)$, where g is the acceleration of gravity, $f(x_2)$ is the latitude-dependent Coriolis parameter, $\eta(x, t)$ is sea surface height anomaly from AVISO, and $\phi(x, t)$ is such that $v(x, t)$ is nondivergent in the interior and its normal projection at the coastline vanishes. The steady $\eta(x, t)$ component is given by a mean dynamic topography constructed from altimetry data, in situ measurements, and a geoid model. The transient component was given by gridded altimetric SSH anomaly measurements provided weekly at 0.25° -resolution. The satellites used, Jason-1 and -2 and Cryosat-2, traversed the Gulf of Mexico approximately 10 times per week during the study period.

ACKNOWLEDGMENTS. We thank the editor and three anonymous reviewers for their constructive comments. This research was made possible by a grant from BP/The Gulf of Mexico Research Initiative.

- Crone TJ, Tolstoy M (2010) Magnitude of the 2010 Gulf of Mexico oil leak. *Science* 330(6004):634.
- Mezić I, Loire S, Fonoberov VA, Hogan P (2010) A new mixing diagnostic and Gulf oil spill movement. *Science* 330(6003):486–489.
- Mariano A, et al. (2011) On the modeling of the 2010 Gulf of Mexico oil spill. *Dyn Atmos Oceans* 52:322–340.
- Olascoaga MJ, Haller G (2012) Forecasting sudden changes in environmental pollution patterns. *Proc Natl Acad Sci USA* 109(13):4738–4743.
- Maltrud M, Peacock S, Visbeck M (2010) On the possible long-term fate of oil released in the Deepwater Horizon incident, estimated using ensembles of dye release simulations. *Environ Res Lett* 5:1–7.
- Huntley HS, Lipphardt BL, Kirwan AD (2013) Surface drift predictions of the Deepwater Horizon spill: The Lagrangian perspective. *Monitoring and Modeling the Deepwater Horizon Oil Spill: A Record-Breaking Enterprise*, eds Liu Y, Macfadyen A, Ji Z-G, Weisberg RH (American Geophysical Union, Washington, DC), pp 179–195.
- Olascoaga MJ, et al. (2013) Drifter motion in the Gulf of Mexico constrained by altimetric Lagrangian coherent structures. *Geophys Res Lett* 40:6171–6175.
- Morey S, Schroeder W, O'Brien J, Zavala-Hidalgo J (2003) The annual cycle of riverine influence in the eastern Mexico basin. *Geophys Res Lett* 30:1867.
- Walker ND, Wiseman WJ, Jr, Rouse LJ, Babin A (2005) Effects of river discharge, wind stress, and slope eddies on circulation and satellite-observed structure of the Mississippi river plume. *J Coast Res* 21:1228–1244.

10. Jones CE, Minchew B, Holt B, Hensley S (2011) Studies of the Deepwater Horizon oil spill with the UAVSAR radar. *Monitoring and Modeling the Deepwater Horizon Oil Spill: A Record-Breaking Enterprise*, eds Liu Y, Macfadyen A, Ji Z-G, Weisberg RH (American Geophysical Union, Washington, DC), pp 33–50.
11. Klein P, Lapeyre G (2009) The oceanic vertical pump induced by mesoscale and sub-mesoscale turbulence. *Annu Rev Mar Sci* 1:351–375.
12. Levy M, Ferrari R, Franks P, Martin A, Riviere P (2012) Bringing physics to life at the submesoscale. *Geophys Res Lett* 39:L14602.
13. McWilliams J (2008) Fluid dynamics at the margin of rotational control. *Environ Fluid Mech* 8:441–449.
14. Fox-Kemper B, et al. (2011) Parameterization of mixed-layer eddies: III. Implementation and impact in global ocean climate simulations. *Ocean Model* 39:61–78.
15. Nikurashin M, Vallis GK, Adcroft A (2013) Routes to energy dissipation for geostrophic flows in the Southern Ocean. *Nat Geosci* 6:48–51.
16. Müller P, McWilliams J, Molemaker M (2005) Routes to dissipation in the ocean: The two-dimensional/three-dimensional turbulence conundrum. *Marine Turbulence: Theories, Observations, and Models. Results of the CARTUM Project*, eds Baumert HZ, Simpson J, Sündermann J (Cambridge Univ Press, Cambridge, UK), pp 397–405.
17. Capet X, McWilliams J, Molemaker M, Shchepetkin A (2008) Mesoscale to sub-mesoscale transition in the California Current System: I flow structure, eddy flux and observational tests. *J Phys Oceanogr* 38:29–43.
18. Fox-Kemper B, Ferrari R, Hallberg R (2008) Parameterization of mixed-layer eddies. Part I: Theory and diagnosis. *J Phys Oceanogr* 38:1145–1165.
19. Taylor J, Ferrari R (2011) Ocean fronts trigger high latitude phytoplankton blooms. *Geophys Res Lett* 38:L23601.
20. D'Asaro E, Lee C, Rainville L, Harcourt R, Thomas L (2011) Enhanced turbulence and energy dissipation at ocean fronts. *Science* 332(6027):318–322.
21. Poje AC, Haza AC, Özgökmen TM, Magaldi M, Garraffo Z (2010) Resolution dependent relative dispersion statistics in a hierarchy of ocean models. *Ocean Model* 31:36–50.
22. Haza AC, Özgökmen TM, Griffa A, Garraffo Z, Piterberg L (2012) Parameterization of particle transport at submesoscales in the Gulf Stream region using Lagrangian subgridscale models. *Ocean Model* 42:31–49.
23. Özgökmen TM, et al. (2012) On multi-scale dispersion under the influence of surface mixed layer instabilities and deep flows. *Ocean Model* 56:16–30.
24. Zhong Y, Bracco A, Villareal T (2012) Pattern formation at the ocean surface: Sargassum distribution and the role of the eddy field. *Limnol Oceanogr Fluids Environ* 2: 12–27.
25. Shcherbina A, et al. (2013) Statistics of vertical vorticity, divergence, and strain in a developed submesoscale turbulence field. *Geophys Res Lett* 40:4706–4711.
26. Sanford T, Kelly K, Farmer D (2011) Sensing the ocean. *Phys Today* 64(2):24–28.
27. Özgökmen TM, Fischer P (2012) CFD application to oceanic mixed layer sampling with Lagrangian platforms. *Int J Comput Fluid Dyn* 26:337–348.
28. Ducet N, Traon PL, Reverdin G (2000) Global high-resolution mapping of ocean circulation from TOPEX/Poseidon and ERS-1 and -2. *J Geophys Res* 105(C8):19,477–19,498.
29. Chavanne C, Klein P (2010) Can oceanic submesoscale processes be observed with satellite altimetry. *Geophys Res Lett* 37:L22602.
30. Callies J, Ferrari R (2013) Interpreting energy and tracer spectra of upper-ocean turbulence in the submesoscale range (1–200km). *J Phys Oceanogr* 43:2456–2474.
31. Monin A, Yaglom A (1971) *Statistical Fluid Mechanics: Mechanics of Turbulence* (MIT Press, Cambridge, MA), Vol I.
32. Babiano A, Basdevant C, Leroy P, Sadourny R (1990) Relative dispersion in 2-dimensional turbulence. *J Fluid Mech* 214:535–557.
33. Richardson LF (1926) Atmospheric diffusion shown on a distance-neighbour graph. *Proc Royal Soc London Series A* 110:709–737.
34. Batchelor GK (1952) Diffusion in a field of homogeneous turbulence 2. The relative motion of particles. *Proc Camb Philos Soc* 48:345–362.
35. Bennett AF (1984) Relative dispersion: Local and nonlocal dynamics. *J Atmos Sci* 41: 1881–1886.
36. Okubo A (1971) Oceanic diffusion diagrams. *Deep-Sea Res* 18:789.
37. LaCasce JH, Ohlmann C (2003) Relative dispersion at the surface of the Gulf of Mexico. *J Mar Res* 61:285–312.
38. Koszalka J, LaCasce JH, Orvik KA (2009) Relative dispersion statistics in the Nordic Seas. *J Mar Res* 67:411–433.
39. Lumpkin R, Elipot S (2010) Surface drifter pair spreading in the North Atlantic. *J. Geophys. Res. Oceans* 115:C12017.
40. Schroeder K, et al. (2012) Targeted Lagrangian sampling of submesoscale dispersion at a coastal frontal zone. *Geophys Res Lett* 39:L11608.
41. Davis R (1985) Drifter observations of coastal currents during CODE. The method and descriptive view. *J Geophys Res* 90:4741–4755.
42. Obukhov A (1941) Spectral energy distribution in a turbulent flow. *Dokl Akad Nauk SSR* 32:22–24.
43. Sundermeyer M, Ledwell J (2001) Lateral dispersion over the continental shelf: Analysis of dye release experiments. *J Geophys Res* 106:9603–9621.
44. Özgökmen T (2012) CARTE: GLAD experiment CODE-style drifter trajectories (low-pass filtered, 15 minute interval records), northern Gulf of Mexico near DeSoto Canyon, July–October 2012. *Gulf of Mexico Research Initiative*, 10.7266/N7VD6WC8. Available at <https://data.gulfresearchinitiative.org/data/R1.x134.073:0004>. Accessed August 11, 2014.